(11) EP 1 134 641 A1

(12)

## **EUROPEAN PATENT APPLICATION**

(43) Date of publication: 19.09.2001 Bulletin 2001/38

(51) Int Cl.7: **G05D 3/00**, H01L 21/00

(21) Application number: 01104511.9

(22) Date of filing: 02.03.2001

(84) Designated Contracting States:

AT BE CH CY DE DK ES FI FR GB GR IE IT LI LU

MC NL PT SE TR

Designated Extension States:

AL LT LV MK RO SI

(30) Priority: 16.03.2000 US 527092

(71) Applicant: Applied Materials, Inc. Santa Clara, California 95054 (US) (72) Inventors:

 Nulman, Jaim Palo Alto, California 94306 (US)


Sidi, Nissim
 Tel Aviv 65132 (IL)

(74) Representative: Käck, Jürgen Kahler, Käck, Fiener et Col. Vorderer Anger 268 86899 Landsberg (DE)

## (54) Apparatus for storing and moving a cassette

(57) A cassette stocker (50) includes a plurality of cassette storage shelves (62a-h) positioned adjacent a cleanroom wall (26) and vertically disposed relative to a plurality of cassette docking stations (40), and a cas-

sette mover (56) to carry a cassette (100) between the shelves and the docking stations. An interstation transfer apparatus includes a support beam and a transfer arm adapted to carry a cassette (100) between processing stations.



EP 1 134 641 A

#### Description

#### Field of the Invention

[0001] The present invention relates generally to substrate processing, and more particularly to an apparatus for storing and moving substrate cassettes.

## **Background of the Invention**

[0002] Semiconductor devices are made on substrates, such as silicon wafers or glass plates, for use in computers, monitors, and the like. These devices are made by a sequence of fabrication steps, such as thin film deposition, oxidation or nitration, etching, polishing, and thermal and lithographic processing. Although multiple fabrication steps may be performed in a single processing station, substrates must be transported between different processing stations for at least some of the fabrication steps. In addition, random substrates in a particular batch may be tested using metrology devices which require additional stations. Substrates are stored in cassettes for transfer between processing stations, metrology stations and other locations. Although cassettes may be carried manually between processing stations, the transfer of cassettes is typically automated. For example, a cassette may be transported to a processing station in an automatic guided vehicle (AGV), and then loaded from the AGV onto a loading platform in the processing station by a robot. Another robot may extract a substrate from the cassette and transport it into a processing chamber at the processing station. When the fabrication steps are complete, the substrate is loaded back into the cassette. Once all of the substrates have been processed and returned to the cassette, the cassette is removed from the loading platform and transported to another location by the AGV. [0003] In order to ensure that the processing equipment does not sit idle, a nearly continuous supply of unprocessed substrates should be available at the processing station. Unfortunately, many processing stations can hold only a single cassette at the loading platform. Therefore, once all of the substrates in the cassette have been processed, the cassette must be quickly replaced, either manually or by an AGV, with a new cassette containing unprocessed substrates. Running such a just-in-time cassette inventory system requires either significant operator oversight or a large number of AGVs, thereby increasing the costs of the fabrication

[0004] Therefore, there is a need for a method and apparatus which continuously supplies substrate cassettes to a processing system so that system down time is reduced or eliminated.

#### SUMMARY OF THE INVENTION

[0005] The present invention is defined in claims 1,

17, 18, and 22, respectively. Particular embodiments of the invention are set out in the dependent claims.

[0006] The present invention provides a method and apparatus for storing multiple cassettes at a processing station, ensuring that a nearly continuous supply of unprocessed substrates is available for processing and that the processing equipment does not idle. Multiple cassettes can be stored at a processing station in a front end support frame and a cassette can be moved to one of a plurality of vertically disposed docking stations where substrates are extracted and transferred to the processing equipment. An automation system is mounted or otherwise disposed on the frame to transfer cassettes between docking stations or between processing stations. In another aspect of the invention, cassettes can be transported between different processing stations without the use of an AGV.

[0007] In one aspect of the invention, an apparatus is provided which includes a front end frame having a plurality of vertically disposed docking stations and multiple cassette storage stations. An automated transfer assembly is preferably disposed adjacent the docking stations and the storage stations to move cassettes between the storage stations and the docking stations. Additionally, an automated transfer assembly can be located between processing stations to transfer cassettes between processing stations without the need for manual or AGV assistance. In another aspect of the invention, a method is provided for delivering a continuous supply of cassettes to a processing system. The method preferably includes providing a plurality of vertically disposed docking stations and multiple storage stations and moving cassettes between the storage stations and the transfer stations to ensure that substrates are continually supplied to the processing system. Additionally, a method is provided for transferring cassettes between processing stations to continue the processing sequence without the need for manual or AGV assistance. [0008] Other objects, features and advantages of the present invention will become more fully apparent from the following detailed description of the preferred embodiments, the appended claims and the accompanying drawings.

### BRIEF DESCRIPTION OF THE DRAWINGS

# [0009]

50

55

35

FIG. 1 is a schematic top view of a processing station according to the present invention;

FIG. 2 is a schematic perspective view of a cassette for holding substrates;

FIG. 3 is a schematic perspective view of a cassette stocker according to the present invention:

FIG. 4A is a schematic front view of the cassette stocker of FIG. 3;

FIG. 4B is a schematic front view of the cassette stocker of FIG. 4A with a plurality of cassettes;

FIG. 5A is a schematic side view of the cassette stocker of FIG. 3;

FIG. 5B is a schematic side view of the cassette stocker of FIG. 3A with a plurality of cassettes;

FIG. 6 is a schematic top view of an end effector located over a docking station;

FIGS. 7A, 7B and 7C are schematic perspective views illustrating the end effector of FIG. 6 lifting and moving a cassette;

FIGS. 8A and 8B are schematic front views of the cassette stocker of FIG. 3 illustrating the path the end effector of FIG. 6 takes in moving a cassette between a loading platform and a cassette docking platform;

FIG. 9 is a schematic perspective view of another embodiment of a cassette stocker having a plurality of vertically disposed docking stations;

FIG. 10 is a schematic side view of the cassette stocker of FIG. 9:

FIG. 11 is a schematic side view of the cassette stocker of FIG. 9 with a plurality of cassettes;

FIG. 12 is a schematic front view of two loading and storage stations connected by an interstation transfer mechanism;

FIG. 13 is a schematic front view of a cassette stocker having a single pair of vertically disposed docking stations; and

FIG. 14 is a simplified side schematic view of a cassette stocker having a single pair of vertically disposed docking stations, the doors of which open in opposite directions.

# DETAILED DESCRIPTION OF A PREFERRED EMBODIMENT

[0010] In the following description, the term "substrate" broadly covers any object that is being processed in a semiconductor device processing system. The term "substrate" includes, for example, semiconductor wafers, flat panel displays, glass plates or disks, and plastic workpieces.

[0011] FIG. 1 is a top view of a processing station 20 of the present invention in which one or more substrates 10 are processed. The processing station 20 has a frontend staging area 22 which is separated from a loading and storage area 24 by a cleanroom wall 26. Cleanroom wall 26 separates a cleanroom 28, where loading and storage area 24 is located, from a gray area 30, where a processing system 32 is housed. The loading and storage area 24 is where cassettes of substrates are delivered and loaded/unloaded into/from the processing station 20. Processing system 32 may include one or more load lock chambers 34, a central transfer chamber 36, and a plurality of processing chambers 38. Inside processing chambers 38 the substrate may be subjected to a variety of fabrication steps, such as thin film deposition, oxidation, nitration, etching, thermal processing or lithographic processing. The processing system and

staging area illustrated in FIG. 1 are merely representative. The processing system could have just a single processing chamber, or it could be a device, such as a chemical mechanical polisher, that does not include any processing chambers. In addition, the processing system could include metrology devices instead of or in addition to processing devices.

[0012] Referring to FIGS. 1 and 2, one or more substrates 10 are brought to the loading and storage area 24 of the processing station in a cassette 100. Substrates 10 are supported in cassette 100 in a generally parallel horizontal configuration by slot ridges 102. Substrates may be loaded and unloaded from cassette 100 through an entry port 103 located in a generally flat front face 106 of the cassette. A removable cassette door 104 may be secured to entry port 103 to prevent the substrates from being exposed to contaminants when the cassette is moved between processing stations or stored outside a processing station. Each cassette 100 also includes three cylindrical indentations 108 (shown in phantom and only two of which are visible in FIG. 2) formed in an underside 110 of the cassette. When cassette 100 is stored at the processing station, three support pins will fit into indentations 108 to support the cassette. Two handles 112 (only one is shown in this perspective view) which project from sidewalls 114 may be used to manually carry the cassette. A generally rectangular flange 116 having an L-shaped cross-section projects from a top surface 118 of the cassette. As discussed below, a robotic cassette mover at the processing station may manipulate the cassette by means of flange 116.

[0013] Referring to FIGS. 1-5B, loading and storage area 24 of processing station 20 includes a cassette loading platform 52, two cassette substrate transfer or docking stations 40 located on either side of loading platform 52, and a cassette stocker or storage stations 50 (only partially illustrated in FIG. 1 so that docking stations 40 may be seen) for storing cassettes at the processing station and moving the cassettes to and from loading platform 52 and docking stations 40.

[0014] A cassette 100 may be placed on or removed from loading platform 52 either manually or by an AGV. From the loading platform 52, the cassette 100 may be moved to one of docking stations 40 or into cassette stocker 50. Loading platform 52 has generally the same perimeter shape as a cassette. Three support pins 54 (only two are shown in the side view of FIG. 5A) project vertically from the loading platform 52 to mate with the indentations in the underside of the cassette 100 and thus to secure the cassette on the loading platform 52. [0015] To transfer substrates through the cleanroom wall 26, cassettes 100 (shown in phantom in FIG. 1) may be positioned at one or both docking stations 40. Each docking station 40 includes a docking platform 42 to support a cassette, an opening 46 formed through cleanroom wall 26, a movable door 44 which seals opening 46 when a substrate is not to be transferred

20

25

through opening 46 or when a cassette is not positioned on docking platform 42, and a mechanism to unlock cassette door 104 and retract the door 104 into front-end staging area 22 to provide horizontal access to the substrates stored within the cassette. For example, the moveable door 44 may behave as a "receiver" and receive the cassette door 104 of a cassette, and then move below the opening 46 (carrying the cassette door 104) so as to allow horizontal access through the opening 46 to substrates stored within the cassette. A description of the preferred configuration and operation of docking station 40 may be found in U.S. Patent Application Serial No. 09/012,323, entitled "A Wafer Cassette Load Station", filed January 23, 1998, by Eric A. Nering, et al., assigned to the assignee of the present invention, the entire disclosure of which is incorporated herein by reference.

[0016] Cassette stocker 50 includes a frame 60 that supports one or more storage racks 58 (shown in FIG. 4A and not illustrated in FIG. 1 so that the docking stations may be shown), and a robotic cassette mover 56 to move the cassettes between the storage rack 58, the loading platform 52, and the docking platforms 42. Frame 60 may be bolted to the floor of cleanroom 28 and/or secured to the cleanroom wall 26. The frame 60 is at least partially disposed below the docking platforms 42 and loading platform 52 so that the footprint of processing station 20 is minimally increased if increased at all.

[0017] Storage rack 58 may include a vertical column of support shelves 62 above each of the two docking stations 40. Each column may include, for example, one, two, three or more individual support shelves 62. Thus, storage rack 58 shown in FIGS. 3-5b provides storage space for six cassettes 100 in support shelves 62a-62h (see FIG. 4B). Each support shelf, such as support shelf 62a, may be a horizontally oriented plate having substantially the same perimeter shape as the cassette 100. Three support pins 64 (only two are shown in the side view of FIG. 5A) project vertically from the support shelf 62 and are positioned to mate with receiving indentations 108 in the underside of the cassette 100. Two vertical posts 66 may be used to secure the outer edge of each support shelf 62a-62h to frame 60. Additionally, the support shelves 62 could be secured to the cleanroom wall for additional support.

[0018] Robotic cassette mover 56 is used to move cassettes 100 between the storage shelves 62, the loading platform 52 and the docking platforms 42. The robotic cassette mover 56 includes a vertically movable end effector 72 which is attached to a horizontally movable support strut 74. The support strut 74 permits arbitrary horizontal movement of end effector 72 in a plane parallel to cleanroom wall 26. The bottom of support strut 74 may be secured to a lateral slider 76 which can move horizontally along a horizontal guide 78 that is attached to or formed as part of frame 60. The lateral slider 76 may be driven from side-to-side by a horizontal lead

screw 80, which is rotated by a horizontal drive motor 82. The horizontal drive motor 82 may be secured to frame 60. Similarly, end effector 72 may be attached to a vertical slider 84 (FIG. 4B) which can slide vertically along a vertical guide 86 (FIG. 5B) attached to or formed as part of support strut 74. The vertical slider 84 may be driven up and down by a vertical lead screw 87 (shown in phantom in FIGS, 4A-5B) which may be rotated by a vertical drive motor 88. The vertical drive motor may be supported by lateral slider 76. Horizontal drive motor 82 and vertical drive motor 88 may be connected to a control system (not shown), such as a programmable digital computer, to control the vertical and horizontal motion of end effector 72. The actuators which drive the movement of the end effector 72 may include stepper motors, pneumatic actuators and other devices known to impart movement in a controllable manner. In addition, a belt drive assembly or other known mechanism can be utilized to drive the sliders both vertically and horizontally. [0019] Referring to FIGS. 6-7A, end effector 72 projects horizontally from support strut 74 toward cleanroom wall 26. The end effector 72 includes a generally flat, hook-shaped finger 90 that defines a rectangular gap 92 which is open on one side of the end effector 72. The end effector 72 is adapted to engage a portion of a cassette 100 through the use of the open end of the end effector 72. In order to transport cassette 100, end effector 72 is vertically positioned between flange 116 and top surface 118 of cassette 100. Referring to FIG. 7B, the end effector 72 is moved laterally so that a base 117 of flange 116 fits into gap 92. Finally, referring to FIG. 7C, end effector 72 is moved vertically upward so that an inner rim 94 of the end effector 72 contacts an underside 119 of flange 116 to lift the cassette 100. The end effector 72 may then be moved laterally to carry cassette 100 to another support shelf 62 or to the loading platform 52 or to a docking platform 42.

[0020] Referring to FIGS. 7A-8A, a cassette 100 may be transported from loading platform 52 to a support shelf, such as support shelf 62c. With support strut 74 positioned to the side of loading platform 52, a cassette 100 is loaded onto the loading platform 52, either manually or by an AGV. To lift the cassette 100 off loading platform 52, end effector 72 is positioned to the left of the cassette at a vertical height between upper surface 118 of the cassette 100 and the lower surface of flange 116. The support strut 74 moves rightwardly until end effector 72 engages the support flange (phantom line A). Then, the end effector 72 moves upwardly to raise the cassette 100 off of the loading platform 52 (phantom line B). To move the cassette 100 to one of the support shelves, e.g., support shelf 62c, end effector 72 raises the cassette 100 until the cassette 100 is generally aligned above the support shelf 62c, with sufficient vertical clearance to permit the underside of the cassette 100 to move horizontally over support pins 64 (phantom line C). Then support strut 74 is moved leftwardly to position the cassette 100 over the support shelf 62c, and

the end effector 72 moves downwardly until the cassette 100 rests on support pins 64 (phantom line D). The end effector 72 may be withdrawn by moving it leftwardly until it clears the flange 116, and then moving it upwardly and rightwardly between the top of the flange 116 and the bottom of support shelf 62b (phantom line E).

[0021] Referring to FIG. 8B, in order to remove the cassette 100 from support shelf 62c, these steps are generally repeated in reverse order. Specifically, end effector 72 moves leftwardly between the top of flange 116 and the bottom of support shelf 62b (phantom line F), downwardly until the end effector 72 is located at a vertical position between the top surface of the cassette 100 and the underside of the flange 116 (phantom line G), and rightwardly until it engages the flange 116 (phantom line H). Then the end effector 72 moves upwardly to lift the cassette 100 off the support plate 62b and then rightwardly to carry the cassette 100 into the vertical channel between the storage racks 58 (phantom line I). From this position, the cassette 100 may be moved up or down and then left or right to a new storage shelf, to one of the docking platforms 42, or to the loading platform 52.

[0022] In the embodiments described in FIGS. 7A-8B, hook-shaped finger 90 of end effector 72 curves to the right so that rectangular gap 92 is open on the right. Of course, if hook-shaped finger 90 curved to the left so that rectangular gap 92 was open on the left, then the relative lateral motion of the end effector to engage and disengage the cassette 100 would be reversed. For example, to lift the cassette 100 from a support shelf 62b, the end effector 72 would be positioned on the right side of the cassette 100 and moved leftwardly to engage the flange 116.

[0023] Referring to FIGS. 1-3, in operation a cassette 100 is transported to processing station 20 and placed on loading platform 52, e.g., manually or by an AGV. The robotic cassette mover 56 transports the cassette from the loading platform 52 to one of the docking stations 40, which aligns the front face of the cassette 100 with docking station door 44. Docking station door 44 then retracts, opening cassette door 104 so that entry port 102 mates with opening 46 in cleanroom wall 26. A wafer handling robot 48 in front-end staging area 22 extracts the substrates from the cassette 100 through opening 46 in the cleanroom wall 26 and inserts the substrates into one of the load lock chambers 34. A robot 39 in transfer chamber 36 moves substrates between the load lock 34 and the processing chambers 38. When the fabrication steps are complete, wafer handling robot 48 extracts the substrate from one of the lock load chambers 34, and returns the substrate to cassette 100 through opening 46 in cleanroom wall 26. Once all of the substrates have been processed, cassette door 104 is closed, the cassette 100 is moved to storage rack 58 or loading platform 52, and a new cassette 100 containing unprocessed substrates is loaded onto the docking station 40.

[0024] As stated above, the processing system could perform inspection processes using metrology devices instead of or in addition to fabrication steps. Metrology stations typically sample and test processed and/or unprocessed wafers stored within the wafer cassettes 100. Typically, a metrology station may test as few as one wafer within each wafer cassette 100 selected for metrology, the cassette 100 being selected randomly or based on some pre-determined selection criteria according to standard metrology principles. Accordingly, each wafer cassette 100 presented for metrology may have significantly less resident time at a particular docking station 40 operated in connection with a metrology station than if the wafer cassette 100 were presented for processing in a processing station. As a result, the time required to open and close the doors and the time required to move a first cassette 100 from the docking station 40 and replace the first cassette 100 with a second cassette 100 may result in undesirable downtime of the metrology station if only one or two docking stations 40 are employed. Further, certain processing stations, particularly those with short processing times, may also have unnecessary downtime as a result of using only one or two docking stations 40.

[0025] Therefore, it may be desirable to incorporate a plurality of vertically stacked docking stations in connection with each storage rack 58. FIGS. 9-11 illustrate a stacked docking station embodiment of a loading and storage area 24 of processing station 20 having two lower substrate docking stations 40 and two upper substrate docking stations 540. As in the previous embodiments, the loading and storage area 24 of processing station 20 includes a cassette loading platform 52, two lower cassette docking or substrate transfer stations 40 located on either side of loading platform 52, and cassette stocker or storage stations 50 for storing cassettes 100 at the processing station and moving the cassettes 100 to and from loading platform 52 and docking stations 40. This embodiment, however, also includes two upper cassette docking or substrate transfer stations 540 each of which is located above one of the docking stations 40. The docking stations thus at least partially overlap, and preferably completely overlap, in footprint. The vertically disposed docking stations are also vertically disposed relative to one or (preferably) more of the support shelves 62.

[0026] According to this embodiment, a cassette 100 may be placed onto or removed from loading platform 52 either manually or by an AGV. To transfer substrates through the cleanroom wall 26, cassettes 100 may be positioned at one of the lower docking stations 40 or also at one of the upper docking stations 540. Each lower docking station 40 includes a lower docking platform 42 to support a cassette 100, a lower opening 46 formed through cleanroom wall 26, a lower movable door 44 which seals lower opening 46 when a substrate is not to be transferred through lower opening 46 or when a cassette 100 is not positioned on lower docking platform

25

42, and a mechanism to unlock cassette door 104 and

retract the door 104 into front-end staging area 22 so as to provide horizontal access to the substrate. Each upper docking station 540 likewise includes an upper docking platform 542 to support a cassette, an opening 546 formed through cleanroom wall 26, an upper movable door 544 which seals upper opening 546 when a substrate is not to be transferred through upper opening 546 or when a cassette 100 is not positioned on upper docking platform 542, and a mechanism to unlock cassette door 104 and retract the door 104 into front-end staging area 22 to provide horizontal access to the substrate. [0027] Upper docking station 540 is of similar construction and operation as lower docking station 40. Similarly, upper movable door 544 is of similar construction and operation as lower movable door 44. Suitable space is provided between upper opening 546 and lower opening 46 so that downward movement of the upper movable door 544 does not interfere with the operation of lower movable door 44 as will be readily appreciated by one of ordinary skill in the art. In an alternative embodiment, upper movable door 544 could be arranged to open upwardly allowing the two doors 44, 544 and the two docking stations 540, 40 to be located closer together (as shown in FIG. 14). It will also be readily appreciated by one of ordinary skill in the art that transport of the cassette 100 to upper docking platform 542 and operation of the system are similar to that described in other embodiments. The embodiment described herein has an upper and lower docking station 40, 540 associated with each of the storage racks 58. However, it should be noted that a plurality of upper docking stations 540 may be used limited only by available vertical space. Further, the upper docking station 540 and the lower docking station 40 may be separated by one or more of the support shelves 62, or both the upper and lower docking stations may be positioned above one or

[0028] The embodiment described above also includes two storage racks 58 disposed above two pairs of docking stations 40, 540 and a loading station 52 disposed between the two docking stations. Preferably, six cassette support shelves 62a-f are disposed above the docking stations 40, 540. While this configuration is believed to provide the highest throughput of substrates in the available space, the invention also includes a single pair of docking stations 40, 540 as shown in FIG. 13 with one or more cassette support shelves 62 disposed in proximity to the docking stations 40, 540.

more of the plurality of storage shelves 62.

[0029] FIG. 9 is a perspective view of one embodiment of the invention having two pairs of docking stations 40, 540 and three storage shelves 62a-c or 62 df disposed above each of the pair of docking stations 40, 540. While three support shelves 62a-c or 62d-f are shown, only one support shelf 62a or 62d could also be used advantageously. Components which form a part of the earlier described embodiments are identified using the same reference numerals. FIGS. 10 and 11 further

depict docking stations 40, 540 and storage shelves 62a-c in a side view, shown with and without cassettes, respectively. Referring to FIG. 12, an interstation transfer apparatus 120 may be used to move cassettes 100 between adjacent processing stations 20' and 20", thereby eliminating the need for AGVs or manual transport. Interstation transfer apparatus 120 includes an overhead support beam 122 which may be secured to posts 66' and 66" of adjacent cassette stockers 50' and 50". A transfer arm 124 may be attached to a slider 126 that moves horizontally along a guide 127 that is attached to or formed as part of support beam 122. The slider 126 may be moved horizontally by a lead screw 130 which may be rotated by a horizontal drive motor 132. An end effector 128 may be connected to transfer arm 124 by a pneumatic actuator 134 to provide end effector 128 with a short vertical stroke.

[0030] In order to transport the cassettes 100 between adjacent processing stations 20', 20", the cassette 100 is moved by robotic cassette mover 56' to the upper right-hand support shelf, i.e., support shelf 62e', of cassette stocker 50'. End effector 128 moves horizontally over flange 116, then down to a vertical position between the bottom of the flange and the top of the cassette. Then the end effector 128 moves to the right until it engages the cassette flange 116. End effector 128 lifts the cassette 100 off support plate 62e', and horizontal drive motor 132 drives the transfer arm 124 rightwardly until the cassette 100 is located over the upper left-hand support shelf 62a" of cassette stocker 50". Finally, the end effector 128 lowers the cassette 100 onto support shelf 62a" and withdraws.

[0031] Interstation transfer apparatus 120 provides an extremely simple method of transferring cassettes 100 between adjacent processing stations 20', 20". This may be particularly useful where one of the processing stations is a metrology station (which could be located entirely inside the cleanroom 28), since it permits the metrology measurements to be made without building a metrology apparatus into the processing equipment 20', 20" and without using a factory automation system 22. [0032] Although cassette stockers 50' and 50" are illustrated as positioned against the same cleanroom wall 26, the interstation transfer apparatus 120 could include rotary mechanisms to allow handoff between end effectors 128 on different support beams. This would permit processing stations 20' and 20" to be positioned around the comers or at opposite walls of the cleanroom.

[0033] The embodiments described above include two storage racks 58, each disposed above docking stations 40, 540 and a loading station 52 disposed between the two storage racks 58. Preferably, six cassette support shelves 62a-f are disposed above each of the one or more docking stations. While this configuration is believed to provide the highest throughput of substrates in the available space, the invention also includes a single pair of docking stations 40, 540 with one or more cassette support shelves 62 disposed in proximity to the

25

30

docking stations 40, 540. FIGS. 13 and 14 are front views of cassette stockers having a single pair of docking stations 40, 540 and two storage shelves 62a-b disposed above the docking stations 40, 540. The upper moveable door 544 opens downwardly in FIG. 13, and upwardly in FIG. 14. When the upper door 544 opens upwardly as shown in FIG. 14, the two docking stations 540, 40 can be located closer together so as to reduce the overall height of the cassette stocker. In both embodiments of FIGS. 13 and 14 support shelve 62a is shown in phantom to indicate that only one support shelf 62b could be advantageously used. An enclosure 550 is disposed about the docking stations 40, 540, the loading station 52 and the cassette support shelves 62. Components which form a part of the earlier described embodiments are identified using the same numbers. [0034] Substrates may be loaded into the system 20 at either a docking station 40, 540 position, at any one of the storage shelf positions 62 or at a loading station 52. The loading station 52 could be disposed adjacent either a support shelf 62 or a docking station 40, 540. The substrate mover system described above with reference to the other embodiments is utilized with the single stack embodiment of FIG. 13 and operates in the same manner except that support shelves 62 disposed in a single stack eliminate the transfer sequence from the additional stack.

[0035] Each of the embodiments described herein utilizes available space above or below docking stations, thereby increasing the storage capability of the system without increasing the footprint (area occupied by the system measured in terms of floor space) of the system. Although the storage shelves shown herein are located above the pair of docking stations, it will be understood that one or more storage shelves could be located below, or between the plurality of vertically disposed docking stations. Accordingly, a processing system could utilize any configuration of the storage device of the present invention including cassette support shelves disposed adjacent a docking station. Further, although a vertically arranged pair of docking stations is preferably associated with each stack of one or more support shelves, a pair of horizontally disposed docking stations may be associated with each stack of support shelves. In such a horizontal configuration each docking station is coupled to a separate tool. The separate tools are preferably high throughput tools (metrology tools, etc.). Preferably, a cassette mover is also disposed in proximity to the support shelves and the docking station to effect transfer of cassettes between the support shelves and the docking stations. Accordingly, while the present invention has been disclosed in connection with the preferred embodiments thereof, it should be understood that other embodiments may fall within the spirit and scope of the invention, as defined by the following claims.

#### Claims

- An apparatus for storing substrate cassettes (100), comprising:
  - at least one cassette docking station (40) for charging and/or discharging substrates (10) from the cassette (100);
  - at least one cassette storage shelve (62a-h) adjacent the at least one cassette docking station (40).
- Apparatus of claim 1, wherein at least two docking stations (40) are vertically disposed.
- Apparatus of claim 1 or 2, wherein at least one shelve (62a-h) is positioned above the at least one docking station (40).
- Apparatus of claim 1, 2 or 3, wherein one or more of the shelves (62a-h) are positioned vertically below the at least one docking station (40).
- Apparatus of any of the preceding claims, wherein the shelves (62a-h) are positioned adjacent a wall, preferably a cleanroom wall (26).
- Apparatus of claim 3, 4 or 5, wherein a plurality of shelves (62a-h) are arranged in a vertical column above the at least one docking station (40).
- Apparatus of any of the preceding claims, comprising:
  - a cassette mover (56) to carry at least one cassette (100) between the at least one shelve (62a-h) and the at least one docking station (40).
- Apparatus of claim 7, wherein the cassette mover (56) is disposed adjacent the at least one shelve (62a-h) and the at least one docking station (40).
- Apparatus of claim 7 or 8, wherein the cassette mover (56) includes a support member (74) positioned adjacent the shelves and moveable in a plane parallel to the shelves (62a-h).
- 10. Apparatus of claim 7, 8 or 9, wherein a plurality of storage shelves (62a-h) are arranged in adjacent vertical columns and are separated by a vertical channel, and the cassette mover (56) is configured to transport a cassette (100) to a selected shelf by moving the cassette (100) vertically through the channel to position the cassette (100) substantially adjacent and at a higher elevation than the selected shelf, and then horizontally to position the cassette (100) over the selected shelf.
- 11. Apparatus of any of the claims 7 to 10, the cassette

15

20

30

mover (56)comprising:

engaging means (72) configured to engage and disengage at least one cassette (100).

- Apparatus of any of the preceding claims, wherein each shelve (62a-h) includes holding elements (4) to engage a cassette (100) positioned on the shelf.
- 13. Apparatus of any of the preceding claims, comprising a loading station (52).
- Apparatus of any of the preceding claims, comprising:

an enclosure disposed about the at least one docking station (40) and the at least one cassette storage shelve (62a-h) and/or the loading station (52).

- 15. Apparatus of any of the preceding claims, wherein the apparatus is located in a cleanroom (28).
- Apparatus of any of the preceding claims, wherein at least two docking stations (40) are vertically disposed and

an upper one of the vertically disposed docking stations (40) comprises a door (544) adapted to open upwardly, and

a lower one of the vertically disposed docking stations (40) comprises a door (44) adapted to open downwardly.

17. A semiconductor processing station, comprising:

a processing system (20) to perform a process 35 on a substrate (10);

an interface wall (26) separating the processing system from a cleanroom (28);

an apparatus for storing cassettes (100) according to any of the preceding claims;

an opening (46, 546)) in the interface wall (26), the opening positioned between the docking station (40) and the processing system (20); and

a wafer transfer robot (48) to transfer a substrate (10) through the opening between the docking station (40) and the processing system (20).

18. A fabrication system, comprising:

a first processing station (20') to perform a process on a substrate (10), the first processing station having a first cassette storing apparatus (50') according to any of the claims 1 to 16; a second processing station (20") to perform a process on a substrate (10), the second processing station having a second cassette

storing apparatus (50") according to any of the claims 1 to 16; and

an interstation cassette mover (120) to transport a cassette (100) between one of the plurality of shelves (62a-h) of the first processing station (20') and one of the plurality of shelves (62a-h) of the. second processing station (20").

- The fabrication system of claim 18, wherein the first processing station (20') performs a first fabrication step.
- The fabrication system of claim 18, wherein at least one of the first and second processing stations (20', 20") is a metrology system.
- 21. The fabrication system of claim 18, 19 or 20, wherein the shelves (62a-h) and the first and second docking stations (40) are arranged in vertical columns, and the interstation cassette mover (120) transports a cassette (100) between a topmost shelf of each of the first and second processing stations (20', 20").
- 25 22. A method of operating a processing station, comprising:

storing a plurality of cassettes (100) on a plurality of cassette storage shelves (62a-h) adjacent a cleanroom wall (26) the shelves (62a-h) being disposed vertically relative to a pair of vertically disposed docking stations (40);

carrying one of the cassettes (100) to one of the docking stations (40) with a cassette mover (56);

removing a substrate (10) from the cassette (100);

performing a metrology process on the substrate: and

returning the cassette (100) to the cassette storage shelves (62a-h) with the cassette mover (56).

50





Fig. 1






Fig. 4A







Fig. 4B










Fig. 8A






Fig. 8B








Fig. 11




Fig. 12





Fig. 13





# **EUROPEAN SEARCH REPORT**

Application Number EP 01 10 4511

		DERED TO BE RELEVANT	<del></del>	<del> </del>	
Category	Citation of document with of relevant pas	indication, where appropriate, sages	Relevant to claim	CLASSIFICATION OF THE APPLICATION (Int.CL7)	
X	WO 99 54921 A (VAR EQUIPMENT) 28 Octo * the whole docume	per 1999 (1999-10-28)	1-17	G05D3/00 H01L21/00	
A	The more documen	***	18-21		
х	US 5 980 183 A (FO: 9 November 1999 (19 * the whole document	999-11-09)	1-17,22		
A	WO 99 60614 A (APPI 25 November 1999 (1 * the whole documer	.999-11-25)	18-21		
				TECHNICAL FIELDS	
- 1				SEARCHED (Int.Cl.7)	
	·				
	The present search report has b	een drawn up for all claims	1		
ı	ince of search	Date of completion of the search	<del>'</del>	Examiner	
MUNICH		19 June 2001	Helot, H		
X : particu Y : particu docum A : techno O : non-w	EGORY OF CITED DOCUMENTS larly relevant if taken alone larly relevant if combined with anoth ant of the same category logical background ritten disclosure dilate document	E : earlier patent doc after the filing dat  D : document cited in L : document cited in  & : member of the se	T: theory or principle underlying the Invention E: earlier patent document, but published on, or after the filing date D: document cited in the application L: document cited for other reasons  &: member of the same patent family, corresponding document		

PO FORM 1503 03.

## ANNEX TO THE EUROPEAN SEARCH REPORT ON EUROPEAN PATENT APPLICATION NO.

EP 01 10 4511

This annex lists the patent family members relating to the patent documents cited in the above-mentioned European search report. The members are as contained in the European Patent Office EDP file on The European Patent Office is in no way liable for these particulars which are merely given for the purpose of information.

19-06-2001

Patent document cited in search report		Publication date		Patent family member(s)	Publication date
WO 9954921	A	28-10-1999	US EP	6079927 A 1080487 A	27-06-200 07-03-200
US 5980183	Α	09-11-1999	EP WO	1028905 A 9846503 A	23-08-2000 22-10-1990
₩O 9960614	A	25-11-1999	EP	1082755 A	14-03-200
			٠		

b For more details about this annex : see Official Journal of the European Patent Office, No. 12/82

FORM POSS